SmartCool V7.30 BMS Points



			Analogue Varia	bles		
BMS Address	Modbus Address	BacNet Address	Variable name	Description	Units	Read/Write
3	3	3	Volt_Step_Change_Evap	Rate of change for voltage step on inverter compressor (Evan Temp)		R/W
19	19	19	Ambient_Air_Hum_Absolute	Ambient air humidity - absolute value		R
20	20	20	Mixed_Air_Hum_Absolute	Mixed air humidity - absolute value		R
21	21	21	Return_Hum_Relative	Return air humidity - relative value		R
22	22	22	Liquid_Press_C1_msk	liquid pressure circuit 1		R
23	23	23	Return_Air_Temp_msk	return air temperature		R
24	24	24	Supply_Air_Temp_msk	supply air temperature		R
25	25	25	Dis_Temp_C1	discharge temperature circuit 1		R
26	26	26	Liquid_Press_C2_msk	liquid pressure circuit 2		R
27	27	27	Supply_Water_Temp_msk	supply water temperature	°C	R
28	28	28	Sel_Set_Temp_msk	temperature setpoint	°C/°F	R/W
29	29	29	Sel_Set_Humid	humidity setpoint		R/W
30	30	30	SET_COND	condensing pressure setpoint		R
31	31	31	DC_Setpoint_msk	dry cooler head pressure setpoint	°C/°F	R/W
32	32	32	Suction_Temp_A1	driver 1 suction temperature		R
33	33	33	Evaporation_Press_A1_msk	evaporation pressure valve A		R
34	34	34	Superheat_A1	superheat valve A		R
35	35	35	Evaporation_Temp_A1_msk	evaporation temperature valve A		R
36	36	36	Suction_Temp_A_2	suction temperature valve A2		R
37	37	37	Evaporation_Press_A_2_msk	evaporation pressure valve A2		R
38	38	38	Superheat_A_2	superheat valve A2		R
39	39	39	Evaporation_Temp_A_2_msk	evaporation temperature valve A2		R
40	40	40	Volts_L1_N	readings from power meter: phase voltage L1-N		R
41	41	41	Volts_L2_N	readings from power meter: phase voltage L2-N		R
42	42	42	Volts_L3_N	readings from power meter: phase voltage L3-N		R
43	43	43	Volts_L1_L2	readings from power meter: line voltage L1-L2		R
44	44	44	Volts_L2_L3	readings from power meter: line voltage L2-L3		R
45	45	45	Volts_L3_L1	readings from power meter: line voltage L3-L1		R
46	46	46	Amps_L1	readings from power meter: phase 1 amperage		R
47	47	47	Amps_L2	readings from power meter: phase 2 amperage		R
48	48	48	Amps_L3	readings from power meter: phase 3 amperage		R
49	49	49	True_Power	readings from power meter: true power		R
50	50	50	Total_kWh_LW	readings from power meter: total kWh low component		R
51	51	51	Ambient_Air_Hum_rH	Ambient air humidity		R
52	52	52	Power_Factor	readings from power meter: power factor		R
53	53	53	Frequency	readings from power meter: frequency		R
54	54	54	Air_Sec	air flow per second		R
55	55	55	CW_Valve_C1	chilled water valve circuit 1 - 0-100.0		R
56	56	56	CW_Valve_C2	chilled water valve circuit 2		R
57	57	57	HPC_C1_Fan	condenser fan speed circuit 1		R
58	58	58	HPC_C2_Fan	condenser fan speed circuit 2		R
59	59	59	Fan_Speed	evaporator fan speed		R
60	60	60	Dry_Fans_OP_C1	dry cooler fan speed circuit 1		R

				1		1
61	61	61	Dry_Fans_OP_C2	dry cooler fan speed circuit 2		R
62	62	62	FC_FAN_DIS	freecooling fan speed		R
63	63	63	Dis_Temp_C2	discharge temperature circuit 2		R
64	64	64	Cond_Temperature_D1_msk	condensing temperature circuit 1		R
65	65	65	Cond_Temperature_D2_msk	condensing temperature circuit 2		R
66	66	66	Frost_Protect_Temp_C2	frost protection temperature - Circuit 2		R
67	67	67	Inlet_CW_Temp_msk	chilled water inlet temperature		R
68	68	68	Frost_Protect_Temp_C1	frost protection temperature - Circuit 1	°C	R
69	69	69	Amb_Temp	ambient temperature		R
70	70	70	CW_DEMAND_DC	dual cool chilled water demand		R
71	71	71	Value_B1	analogue input 1		R
72	72	72	Value_B2	analogue input 2		R
73	73	73	Value_B3	analogue input 3		R
74	74	74	Value_B4	analogue input 4		R
75	75	75	Value_B5	analogue input 5		R
76	76	76	Value_B6	analogue input 6		R
77	77	77	Value_B7	analogue input 7		R
78	78	78	Value_B8	analogue input 8		R
79	79	79	Value_B9	analogue input 9		R
80	80	80	BMS_Anal_Synchro_Point	test variable		R
81	81	81	Aout_1	analogue output 1		R
82	82	82	Aout_2	analogue output 2		R
83	83	83	Aout_3	analogue output 3		R
84	84	84	Aout_4	analogue output 4		R
85	85	85	Aout_5	analogue output 5		R
86	86	86	Aout_6	analogue output 6		R
87	87	87	FC_Valve_OP	freecooling valve current position		R
88	88	88	Freecool_Demand	freecooling demand		R
89	89	89	Discharge_Temp_EVD1_C1	Discharge temperature circuit 1 from EVD1 S4		R
91	91	91	Subcool_CT2_msk	Subcool calculated from converted liquid pressure - liquid		R
92	92	92	Inv_Frequency_C1	inverter frequency circuit 1		R
93	93	93	Control_Temp_msk	Regulation control temperature	°C/°F	R
94	94	94	Inv_Frequency_C2	inverter frequency circuit 2		R
95	95	95	Control_Return_Hum	Regulation control humidity	%	R
96	96	96	Value_B10	analogue input 10	°C	R
97	97	97	SET_TEMP_msk	actual temperature setpoint		R
98	98	98	Set_Temp1_msk	temperature setpoint Z1	°C/°F	R/W
99	99	99	Set_Temp2_msk	temperature setpoint Z2	°C/°F	R/W
100	100	100	Set_Temp3_msk	temperature setpoint Z3	°C/°F	R/W
101	101	101	Set_Temp4_msk	temperature setpoint Z4	°C/°F	R/W
102	102	102	Set_Humid1	humidity setpoint Z1		R/W
103	103	103	Set_Humid2	humidity setpoint Z2		R/W
104	104	104	Set_Humid3	humidity setpoint Z3		R/W
105	105	105	Set_Humid4	humidity setpoint Z4		R/W
106	106	106	SET_COND1_msk	condenser setpoint C1 Z1	°C/°F	R/W
107	107	107	SET_COND2_msk	condenser setpoint C1 Z2	°C/°F	R/W
108	108	108	SET_COND3_msk	condenser setpoint C1 Z3	°C/°F	R/W
109	109	109	SET_COND4_msk	condenser setpoint C1 Z4	°C/°F	R/W
110	110	110	Sel_Set_Cool_msk	temp bias cooling setpoint	°C/°F	R/W
111	111	111	Sel_Set_Heat_msk	temp bias heating setpoint	°C/°F	R/W
111						

	1	1	1			
113	113	113	SET_COND2_C2_msk	condenser setpoint C2 Z2	°C/°F	R/W
114	114	114	SET_COND3_C2_msk	condenser setpoint C2 Z3	°C/°F	R/W
115	115	115	SET_COND4_C2_msk		°C/°F	R/W
116	116	116	Supply_Wtr_Temp_Inlet_Vortex_msk	supply water temperature	°C	R
117	117	117	CPY1_Current	CPY1 current output	Α	R
118	118	118	CPY2_Current	CPY2 current output	Α	R
119	119	119	CPY1_Steam_Production	CPY1 steam production Kg/h	Kg/h	R
120	120	120	CPY2_Steam_Production	CPY2 steam production Kg/h	Kg/h	R
121	121	121	Dehum_Valve_Control	SV unit dehum valve control		R
122	122	122	SV_Dehum_Valve_Position	SV unit dehum valve position feedback		R
123	123	123	Evap_Temp_One_Comp_Limit			R/W
124	124	124	Evap_Temp_two_Comp_Limit			R/W
125	125	125	Fan_Offset_Speed			R/W
126	126	126	Main_Fan_Speed_1	Main Fan speed 1		R/W
127	127	127	Main_Fan_Speed_2	Main Fan speed 2		R/W
128	128	128	Main_Fan_Speed_3	Main Fan speed 3		R/W
129	129	129	td_threshold			R/W
130	130	130	unit_td			R
131	131	131	PROP_TEMP			R
132	132	132	Mixed_Air_Temp	Mixed air Temperature		R
133	133	133	Mixed_Air_Humidity_rH	Mixed air Humidity		R
134	134	134	S1_Probe_Value1	S1 probe value		R
135	135	135	S2_Probe_Value1	S2 probe value		R
136	136	136	S3_Probe_Value_1	S3 probe value		R
137	137	137	S4_Probe_Value1	S4 probe value		R
138	138	138	FC_Control_Temp			R
139	139	139	Gas_Extract_FC_Damper_Position		%	R/W
217	217	217	Demand_OFF_Level	Power demand off level	%	R
330	330	330	A10_SH_SH_msk	Superheat		R/W

			Integer Variabl	es		
BMS Address	Modbus Address	BacNet Address	Variable name	Description	Units	Read/Write
1	208	1001	CURRENT_HOUR	Current hour	h	R
2	209	1002	NEW_HOUR	New hour	h	R/W
3	210	1003	Act_Application_Type	EM24 Actual Application Type		R
4	211	1004	CURRENT_MINUTE	Current minute		R
5	212	1005	NEW_MINUTE	New minute		R/W
6	213	1006	Act_Measuring_System	EM24 Actual Measuring System		R
7	214	1007	CURRENT_DAY	Current day		R
8	215	1008	NEW_DAY	New day		R/W
9	216	1009	Address_Drv1	EVO Driver 1 address		R
10	217	1010	CURRENT_MONTH	Current month		R
11	218	1011	NEW_MONTH	New month		R/W
12	219	1012	Address_Drv2	EVO Driver 2 address		R
13	220	1013	CURRENT_YEAR	Current year		R
14	221	1014	NEW_YEAR	New year		R/W
15	222	1015	Air_flow_input	Air flow input		R
16	223	1016	BMS_Heartbeat	BMS heartbeat signal		R/W
17	224	1017	NEW_WEEKDAY	New weekday	W	R/W
18	225	1018	FreshAir_Damper	Fresh air damper		R
19	226	1019	ReturnAir_Damper	Return air damper		R

20	227	1020	ReturnAir Damper m			R
21	228	1021	Unit_Status	0 = Unit On; 1 = Off By Alarms; 2 = Off By Supervisor; 3 =		R
22	229	1022	I46 HumState	Off Ry Time: 4 = Off Ry Dig Input: 5 = Off Ry Display: 6 = Humidifier status (0 = not active (no request, shutdown		R/W
23	230	1023	I49 Conductivity	or disabled): 1 = start evaporation cycle: 2 = water fill in Actual value of conductivity		R/W
24	231	1024	Diff_Pressure_msk	differential pressure (air)		R
25	232	1025	High_Flow_msk	air flow - high component		R
26	233	1026	Low_Flow_msk	air flow - low component		R
27	234	1027	LP_Al_Start_Delay_SV	an now low component		R/W
28	235	1027	Cooling Stages	Number of DX cooling stages		R
29	236	1029	Heating_type	heating configuration type		R
30	237	1030	Num_Heaters	number of heating banks		R
31	238	1031	X_H_Value_CP1_C1	compressor 1 circuit 1 run hours high		R
32	239	1031		compressor 1 circuit 1 run hours low		R
33	240	1032	X_L_Value_CP1_C1	compressor 2 circuit 1 run hours high		R
34		1033	X_H_Value_CP2_C1			R
35	241		X_L_Value_CP2_C1 X H Value INV C1	compressor 2 circuit 1 run hours low		R
		1035		circuit 1 inverter run hours high		
36	243	1036	X_L_Value_INV_C1	circuit 1 inverter run hours low		R
37	244	1037	X_H_Value_CP1_C2	compressor 1 circuit 2 run hours high		R
38	245	1038	X_L_Value_CP1_C2	compressor 1 circuit 2 run hours low		R
39	246	1039	X_H_Value_CP2_C2	compressor 2 circuit 2 run hours high		R
40	247	1040	X_H_Value_INV_C2	circuit 2 inverter run hours high		R
41	248	1041	X_L_Value_INV_C2	circuit 2 inverter run hours low		R
42	249	1042	X_H_Value_Supply_Fan	supply fan run hours high		R
43	250	1043	X_L_Value_Supply_Fan	supply fan run hours low		R
44	251	1044	X_H_Value_Filter	filter run hours high		R
45	252	1045	X_L_Value_Filter	filter run hours low		R
46	253	1046	Stages_Required	number of DX cooling stages required		R
47	254	1047	C1_Type	circuit 1 configuration - {X;W;C;1;2;}		R
48	255	1048	C1_Comp_Type	circuit 1 compressor type - {0;1;2;V;L;H;X;A;W;D}		R
49	256	1049	C2_Type	circuit 2 configuration - {0;X;W;F;C;1;2;}		R
50	257	1050	C2_Comp_Type	circuit 2 compressor type - {0;1;2;V;L;H;C;F;}		R
51	258	1051	Cooling_Limit	cooling limit		R
52	259	1052	Airflow_Set_H_msk	airflow setpoint high		R
53	260	1053	Airflow_Set_L_msk	airflow setpoint low		R
54	261	1054	HP_Valve_OP_C1	dry cooler valve head pressure output c1		R
55	262	1055	HP_Valve_OP_C2	dry cooler valve head pressure output c2		R
56	263	1056	Thyristor_DEMAND	thyristor heating demand		R
57	264	1057	LPHW_Valve	low pressure hot water valve position		R
58	265	1058	EVO_LP_Alarm_Start_Delay_SV			R/W
60	267	1060	Suct_Val	Suction pressure (absolute)	kPa	R
61	268	1061	Disch_Val	Discharge pressure (absolute)	kPa	R
65	272	1065	X_L_Value_CP2_C2	compressor 2 circuit 2 run hours low		R
66	273	1066	Cont_Void_Press_msk	Constant Pressure - Void Pressure		R
67	274	1067	Total_kWh_HW	readings from power meter: total kWh high component		R/W
68	275	1068	Point_Conversion_WPX	Calculated working point position		R
69	276	1069	Point_Conversion_WPY	Calculated working point position		R
70	277	1070	Room_Pressure			R
71	278	1071	Bios_Month_msk			R/W
72	279	1072	Bios_Day_msk			R/W
73	280	1073	Boot_Month_msk			R/W
76	283	1076	Con_Pressure_U1			R/W

78	285	1078	Oil Alarm Countdown Delay			R/W
79	286	1079	Oil_Critical_Alarm_Delay			R/W
80	287	1080	BMS_Int_Synchro_Point	test variable		R
81	288	1081	Smartcool_Name	SmartCool name - {SC;SL;SN;SR;SD;SV;}		R
82	289	1082	X_H_Value_Humidifier	Humidifier running hours - high value output		R
83	290	1083	X_L_Value_Humidifier	Humidifier running hours - low value output		R
84	291	1084	X_H_Value_Heat	heating run hours high		R
85	292	1085	X L Value Heat	heating run hours low		R
86	293	1086	CP_Start_Counter_C1_lo	nearing rain nears to it		R
87	294	1087	X_L_Value_FreeC	freecooling run hours low		R
88	295	1088	X_H_Value_FreeC	freecooling run hours high		R
89	296	1089	X_L_Value_CWValve1	cw valve c1 run hours low		R
90	297	1090	X_H_Value_CWValve1	cw valve c1 run hours high		R
91	298	1091	X_L_Value_CWValve2	cw valve c2 run hours low		R
92	299	1092	X_L_Value_CWValve2	cw valve c2 run hours high		R
93	300	1093	X L Value Dehum	dehum run hours low		R
94	300	1093	X_L_Value_Dehum	dehum run hours high		R
95	301	1094	Supply Water Temp C2 msk	supply water temperature c2	°C	R R
96	303	1095	PLAN ADDRESS	Address of the controller in the pLAN network		R
97	303	1090	CP_Start_Counter_C2_x1000	Address of the controller in the plan network		R
98	305	1097				R
			CP_Start_Counter_C2_lo			
99	306	1099	CP_Start_Counter_C1_x1000			R
100	307	1100	Damper_Delay_Off			R/W
101	308	1101	C1_Inv_Max_Speed_Both_On	La d'antre de la della of the BIOS		R/W
102	309	1102	BIOS_DATE	Indicates the date of the BIOS		R
103	310	1103	CPY1_Required_Production		%	R
104	311	1104	CPY2_Required_Production		%	R
105	312	1105	unit_td_2			R
106	313	1106	BIOS_RELEASE	Indicates the release of the BIOS		R
107	314	1107	Damper_Alarm_Delay	Address of the controller in a supervisory system network		R/W
111	318	1111	BMS_ADDRESS	Address of the controller in a supervisory system network		R/W
112	319	1112	BMS2_ADDRESS	n 2		R/W
113	320	1113	BOARD_TYPE	Type of the controller		R
114	321	1114	BOOT_DATE	Indicates the date of the BOOT		R
117	324	1117	BOOT_RELEASE	Indicates the release of the BOOT		R
118	325	1118	Evap_Temp_Compensation_3			R
120	327	1120	Boot_Day_msk	Specifies the model of BUILTIN terminal connected to the		R/W
121	328	1121	BUILTIN_TYPE	controller		R
122	329	1122	Strat_Month_msk			R/W
123	330	1123	Strat_Day_msk			R/W
124	331	1124	Startup_Delay			R/W
125	332	1125	Running_Delay			R/W
126	333	1126	Comp_Stop_Delay			R/W
128	335	1128	td_alarm_delay		S	R/W
129	336	1129	TD_delay_all_comps		S	R/W
133	340	1133	C2_valve			R
134	341	1134	C1_valve	Communication speed (haudrate) at the social part of		R
135	342	1135	COM_BAUDRATE_BMS	Communication speed (baudrate) of the serial port n.1 (the none where usually is connected the sunervisory. Communication speed (baudrate) of the serial port n.3		R/W
136	343	1136	COM_BAUDRATE_BMS2	Communication speed (baudrate) of the serial port n.3 (the one where usually is connected the supervisory Communication speed (baudrate) of the serial port n.2		R/W
137	344	1137	COM_BAUDRATE_FIELDBUS	Communication speed (baudrate) of the serial port n.2 (the one where usually is connected the TI AN or Relimo. Communication speed (baudrate) of the serial port n.4		R/W
138	345	1138	COM_BAUDRATE_FIELDBUS2	(the one where usually is connected the TLAN or Relimo		R/W

139	346	1139	COM_PROTOCOL_BMS	Indicates the communication protocol used by serial port	 R/W
140	347	1140	COM_PROTOCOL_BMS2	Indicates the communication protocol used by serial port	 R/W
141	348	1141	COM_PROTOCOL_FIELDBUS	Indicates the communication protocol used by serial port	 R/W
142	349	1142	COM_PROTOCOL_FIELDBUS2	Indicates the communication protocol used by serial port	 R/W

			Digital Variab	les		
BMS Address	Modbus Address	BacNet Address	Variable name	Description	I/O Status	Read/Write
1	1	1	X1C0			R/W
2	2	2	EVD_pCO_Synchro_OK_1	EVD ready to receive the Cooling capacity and starts to regulate the EEV based on the SH		R
3	3	3	SET_HOUR	Request to copy NEW_HOUR into HOUR		R/W
6	6	6	SET_MINUTE	Request to copy NEW_MINUTE into MINUTE		R/W
7	7	7	Reset_FCminOFF			R/W
9	9	9	SET_DAY	Request to copy NEW_DAY into DAY		R/W
10	10	10	Manual_ON_OFF			R/W
12	12	12	SET_MONTH	Request to copy NEW_MONTH into MONTH		R/W
13	13	13	En_Mixed_Air_Temp			R/W
14	14	14	En_Amb_Hum			R/W
15	15	15	SET_YEAR	Request to copy NEW_YEAR into YEAR		R/W
16	16	16	En_Mixed_Air_Hum			R/W
18	18	18	SET_WEEKDAY	Request to copy NEW_WEEKDAY into WEEKDAY		R/W
19	19	19	Inv_Max_Fast_Starts_Reset_1_Al			R/W
20	20	20	Res_Al_by_BMS	reset alarm by BMS		R/W
21	21	21	DI_Remote_On_Off	remote on/off status		R
22	22	22	DI_Airflow_Switch	airflow switch		R
23	23	23	DI_Filter_Change	filter change switch		R
24	24	24	DI_Phase_Rotation	phase rotation		R
25	25	25	DI_Water_Cond_Pump	water condensate pump		R
26	26	26	DI_Fire_Smoke	fire smoke status		R
27	27	27	DI_Leak_Detector	leak detection		R
28	28	28	DI_Over_Heat_Cut_Out	over heat cut out		R
29	29	29	DI_C1_CP1_Status	circuit 1 compressor 1 status		R
30	30	30	DI_C1_CP2_Status	circuit 1 compressor 2 status		R
31	31	31	DI_Low_Pressure_Trip_C1	circuit 1 low pressure trip status		R
32	32	32	DI_Low_Pressure_Trip_C2	circuit 2 low pressure trip status		R
33	33	33	DI_C2_CP1_Status	circuit 2 compressor 1 status		R
34	34	34	DI_C2_CP2_Status	circuit 2 compressor 2 status		R
35	35	35	SUPERV_ONOFF	unit on/off by Supervisor		R/W
36	36	36	AL_OHCO_Manual	Overheat Cutout Alarm - Manual		R
37	37	37	Al_Pos_Bypass_Val_Failure_CT1	Alarm - possible bypass valve failure due to high pressure CT1		R
38	38	38	EVD_OR_Sys_Alarms_2	EVD Alarm Circuit 2		R
39	39	39	Al_Pos_Bypass_Val_Failure_CT2	Alarm - possible bypass valve failure due to high pressure CT1		R
40	40	40	REMOTE_ON_OFF	remote on/off		R
41	41	41	Al_Probe_B1	fault probe 1 alarm		R
42	42	42	Al_Probe_B2	fault probe 2 alarm		R
43	43	43	Al_Probe_B3	fault probe 3 alarm		R
44	44	44	Al_Probe_B4	fault probe 4 alarm		R
45	45	45	Al_Probe_B5	fault probe 5 alarm		R
46	46	46	Al_Probe_B6	fault probe 6 alarm		R
47	47	47	Al_Probe_B7	fault probe 7 alarm		R
48	48	48	Al_Probe_B8	fault probe 8 alarm		R
49	49	49	Al_Probe_B9	fault probe 9 alarm		R

г г					1	ı
50	50	50	Al_Probe_B10	fault probe 10 alarm		R
51	51	51	Al_Airflow	airflow failure alarm		R
52	52	52	AL_CP1_C1_Status	circuit 1 compressor 1 alarm		R
53	53	53	AL_CP2_C1_Status	circuit 1 compressor 2 alarm		R
54	54	54	AL_INV_C1_Status	circuit 1 inverter compressor alarm		R
55	55	55	AL_CP1_C2_Status	circuit 2 compressor 1 alarm		R
56	56	56	AL_CP2_C2_Status	circuit 2 compressor 2 alarm		R
57	57	57	AL_INV_C2_Status	circuit 2 inverter compressor alarm		R
58	58	58	AL_Filter_Change	filter change alarm		R
59	59	59	AL_Phase_Fail	phase failure alarm		R
60	60	60	AL_W_Flood_Tray_Cond_Pump_PhRot	Alarm - Combined water flood, drip tray level, cond		R
61	61	61	MAL_FIRE_SMOKE	fire smoke alarm		R
62	62	62	AL_Leak_Detector	Leak detector alarm		R
63	63	63	AL_OHCO_Auto	Overheat Cutout Alarm - Auto		R
64	64	64	Al_Low_Pressure_Crit_C1	low pressure circuit 1 alarm - critical trips		R
65	65	65	Al_Low_Pressure_Crit_C2	low pressure circuit 2 alarm - critical trips		R
66	66	66	Al_Maint_CP1_C1	circuit 1 compressor 1 maintenance alarm		R
67	67	67	Al_Maint_CP2_C1	circuit 1 compressor 2 maintenance alarm		R
68	68	68	Al_Maint_INV_C1	circuit 1 inverter compressor maintenance alarm		R
69	69	69	Al_Maint_CP1_C2	circuit 2 compressor 1 maintenance alarm		R
70	70	70	Al_Maint_CP2_C2	circuit 2 compressor 2 maintenance alarm		R
71	71	71	Al_Maint_INV_C2	circuit 2 inverter compressor maintenance alarm		R
72	72	72	Al_Maint_Supply_Fan	supply fan maintenance alarm		R
73	73	73	AL_HIGH_HUMID	high humidity alarm		R
74	74	74	AL_LOW_HUMID	low humidity alarm		R
75	75	75	AL_H_Return_Air	high return temperature alarm		R
76	76	76	AL_L_Return_Air	low return temperature alarm		R
77	77	77	AL_H_SUPPLY_TEMP	high supply temperature alarm		R
78	78	78	AL_L_SUPPLY_TEMP	low supply temperature alarm		R
79	79	79	AL_HIGH_PRESS1	circuit 1 high pressure alarm		R
80	80	80	BMS_Dig_Synchro_Point	test variable		R
81	81	81	AL_HIGH_PRESS2	circuit 2 high pressure alarm		R
82	82	82	Al_Step_Motor_D1	driver 1 step motor alarm		R
				·		_
83	83	83	Al_Eeprom_D1	driver 1 EEPROM failure alarm		R
84	84	84	Al_MOP_Delay_D1	driver 1 mop delay alarm		R
85	85	85	Al_LOP_Delay_D1	driver 1 lop delay alarm		R
86	86	86	Al_Low_SHeat_D1	driver 1 low superheat alarm		R
87	87	87	Reset_Supply_Hum_Alarm_BMS	district A little consistency of		R/W
88	88	88	Al_Braha_S1_D1	driver 1 makes at alarm		R
89	89	89	Al_Probe_S1_D1	driver 1 probe s1 alarm		R
90	90	90	Al_Probe_S2_D1	driver 1 probe s2 alarm		R
91	91	91	Al_Probe_S3_D1	driver 1 probe s3 alarm		R
92	92	92	Al_Step_Motor_D2	driver 2 step motor alarm		R
93	93	93	Al_Eeprom_D2	driver 2 EEPROM failure alarm		R
94	94	94	Al_MOP_Delay_D2	driver 2 mop delay alarm		R
95	95	95	Al_LOP_Delay_D2	driver 2 lop delay alarm		R
96	96	96	Al_Low_SHeat_D2	driver 2 low superheat alarm		R
97	97	97	Al_Damper	Damper alarm - not open after set time		R
98	98	98	Al_High_SHeat_D2	driver 2 high superheat alarm		R
99	99	99	Al_Probe_S1_D2	driver 2 probe s1 alarm		R
100	100	100	Al_Probe_S2_D2	driver 2 probe s2 alarm		R

T		1	I		ı
101	101	101	Al_Probe_S3_D2	driver 2 probe s3 alarm	 R
102	102	102	Al_Step_Motor_D3	driver 3 step motor alarm	 R
103	103	103	Al_Probe_S4_D1	driver 1 probe s4 alarm	 R
104	104	104	Al_Probe_S4_D2	driver 2 probe s4 alarm	 R
105	105	105	Al_Step_Motor_D4	driver 4 step motor alarm	 R
106	106	106	Al_Backup_Power_Active	Alarm - backup power supply active	 R
107	107	107	AL_Phase_Fail_UltraCap	phase failure alarm - ultracap	 R
108	108	108	Al_Drv1_OffLine	driver 1 offline alarm	 R
109	109	109	Al_Drv2_OffLine	driver 2 offline alarm	 R
110	110	110	Al_Low_Pressure_EVO_Crit_C1	EVO low pressure circuit 1 alarm - critical trips	 R
111	111	111	Al_Low_Pressure_EVO_Crit_C2	EVO low pressure circuit 2 alarm - critical trips	 R
112	112	112	AL_Clock	controller clock alarm	 R
113	113	113	Al_Frost	frost protection alarm	 R
114	114	114	Al_Supply_Water_Temp	supply water temperature alarm	 R
115	115	115	PM_Offline	power meter offline alarm	 R
116	116	116	Al_Plan	plan disconnected alarm	 R
117	117	117	Al_Mn_CPY1	bottle life timer alarm CPY1	 R
118	118	118	Al_Ec_CPY1	high water conductivity CPY1	 R
119	119	119	Al_E1_CPY1	configuration parameter error CPY1	 R
120	120	120	Al_E0_CPY1	internal memory error CPY1	 R
121	121	121	Al_EH_CPY1	excess electrode current alarm CPY1	 R
122	122	122	Al_EP_CPY1	low steam flow alarm CPY1	 R
123	123	123	Al_EU_CPY1	high water level alarm CPY1	 R
124	124	124	Al_E3_CPY1	no signal connected alarm CPY1	 R
125	125	125	Al_EF_CPY1	no water supply alarm CPY1	 R
126	126	126	Al_ED_CPY1	drain problem alarm CPY1	 R
127	127	127	Al_Su_CPY1	serial connection disconnected alarm CPY1	 R
128	128	128	Al_PreAL_CY_CPY1	cylinder maintenance alarm CPY1	 R
129	129	129	Al_E2_CPY1	E2 memory full alarm CPY1	 R
130	130	130	Al_Pre_EA_CPY1	foam warning alarm CPY1	 R
131	131	131	Al_EH_1_CPY1	excess current alarm CPY1	 R
132	132	132	Al_EL_1_CPY1	low humidity alarm CPY1	 R
133	133	133	Al_Pre_CY_CPY1	lime scale limit steam alarm CPY1	 R
134	134	134	Al_Pre_CL_CPY1	flakes warning alarm CPY1	 R
135	135	135	Al_Warning_ID_Device_CPY1	warning ID device CPY1	 R
136	136	136	Al_Warning_Match_Digit_CPY1	warning match digit CPY1	 R
137	137	137	Al_CPY_Offline_CPY1	CPY1 offline alarm	 R
138	138	138	Damper_Open_Feedback	0=Closed, 1=more than 80% open	 R
139	139	139	Damper_Open_Enable		 R
140	140	140	Comps_On_C1	circuit 1 compressors on	 R
141	141	141	Comps_On_C2	circuit 2 compressors on	 R
142	142	142	FAN_ENABLED	fan enabled	 R
143	143	143	Alarms_on	alarms on	 R
144	144	144	Cool_On	cooling on	 R
145	145	145	Heat_On	heating on	 R
146	146	146	Hum_On_Icon	Humidity ON icon on Main Mask	 R
147	147	147	Dehum_On	dehumidification on	 R
148	148	148	Al_Driver_1	driver 1 alarm	 R
149	149	149	Al Driver 2	driver 2 alarm	 R
150	150	150	Al_Driver_3	driver 3 alarm	 R
151	151	151	Al_Driver_4	driver 4 alarm	 R

				T	_
152	152	152	Al_Drivers	drivers alarm	 R
153	153	153	Al_Hum_CPY1	humidity alarm CPY1	 R
154	154	154	Heater1_Thyr	enable first stage of thyristor heating	 R
155	155	155	STEP_HEATER1	enable heater stage 1	 R
156	156	156	STEP_HEATER2	enable heater stage 2	 R
157	157	157	STEP_HEATER3	enable heater stage 3	 R
158	158	158	GO_Comp_1_C1	start compressor 1 circuit 1	 R
159	159	159	GO_Comp_2_C1	start compressor 2 circuit 1	 R
160	160	160	Al_Low_Pressure_C1	low pressure circuit 1 alarm	 R
161	161	161	Light_Alarms	non critical alarms	 R
162	162	162	Serious_Alarms	critical alarms	 R
163	163	163	GO_Comp_1_C2	start compressor 1 circuit 2	 R
164	164	164	GO_Comp_2_C2	start compressor 2 circuit 2	 R
165	165	165	Al_Low_Pressure_C2	low pressure circuit 2 alarm	 R
166	166	166	HGRH_Valve_Enable	enable hot gas reheat solenoid valve to open coil	 R
167	167	167	En_Dry_Cool_1	dry cooler enabled circuit 1	 R
168	168	168	En_Dry_Cool_2	dry cooler enabled circuit 2	 R
169	169	169	Al_Low_Pressure_EVO_C1	EVO low pressure circuit 1 alarm	 R
170	170	170	AL_Calc_Error1	air flow calculation error alarm	 R
171	171	171	AL_Dis_Temp_C1	discharge gas high temperature c1 alarm	 R
172	172	172	AL_Dis_Temp_C2	discharge gas high temperature c2 alarm	 R
173	173	173	AL_Dis_Temp_C1_Warn	discharge gas high temperature warning c1	 R
174	174	174	AL_Dis_Temp_C2_Warn	discharge gas high temperature warning c2	 R
175	175	175	Al_Dry_C_C1	dry cooler alarm c1	 R
176	176	176	Al_Dry_C_C2	dry cooler alarm c2	 R
177	177	177	Shutdown_Alarms	unit shutdown alarm	 R
178	178	178	Al_Low_Pressure_EVO_C2	EVO low pressure circuit 2 alarm	 R
179	179	179	AL_DC_Low_Inlet_C1	low inlet temperature alarm	 R
180	180	180	Dout_1	digital output status 1 – heating stage 1	 R
181	181	181	Dout_2	digital output status 2 – heating stage 2	 R
182	182	182	Dout_3	digital output status 3 – heating stage 3	 R
183	183	183	Dout_4	digital output status 4 – circuit 1 compressor 1 / dual	 R
184	184	184		nower priority / inverter enable	 R
			Dout_5	digital output status 5 – circuit 1 compressor 2 digital output status 6 – circuit 1 liquid line solenoid	_
185	185	185	Dout_6		 R
186	186	186	Dout_7	digital output status 7 – non critical alarm	 R
187	187	187	Dout_8	digital output status 8 – critical alarm	 R
188	188	188	Dout_9	digital output status 9 – circuit 2 compressor 1	 R
189	189	189	Dout_10	digital output status 10 - circuit 2 compressor 2	 R
190	190	190	Dout_11	digital output status 11 - circuit 1 liquid line solenoid	 R
191	191	191	Dout_12	digital output status 12 – hot gas solenoid valve	 R
192	192	192	Dout_13	digital output status 13 – dual power priority set	 R
193	193	193	Dout_14	digital output status 14	 R
194	194	194	Dout_15	digital output status 15 digital output status 16 – dry cooler pump enable circuit	 R
195	195	195	Dout_16	digital output status 16 – dry cooler pump enable circuit digital output status 17 – dry cooler pump enable circuit	 R
196	196	196	Dout_17	aignai output status 17 – ury cooler pump enable circuit 2	 R
197	197	197	Dout_18	digital output status 18	 R
198	198	198	Syson	unit on/off	 R
199	199	199	Show_B10b	Used for pGDT display	 R/W
200	200	200	Al_Supply_Water_Temp_C2	supply water input temperature alarm	 R
201	201	201	aL_low_oil_Circ1	inverter unit low oil in compressor in circuit 1 alarm	 R
202	202	202	aL_low_oil_Circ2	inverter unit low oil in compressor in circuit 2 alarm	 R

203	203	203	Dis_Comps_Pow_Fail	compressor oil preheat active	 R
204	204	204	Al_LPHW_FP	frost protection alarm	 R
205	205	205	Al_Pumpdown	pump down cycle complete alarm	 R
206	206	206	Al_Inverter_C1_Max_Evap_Temp	compressor 1 max evaporating temperature alarm	 R
207	207	207	Al_Inverter_C2_Max_Evap_Temp	compressor 2 max evaporating temperature alarm	 R